

1 051953 8-22

API NUMBER 15- 033-20,291-00-00

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

S/2 SE NW, SEC. 7, T 31 S, R 17 W/E  
2325 feet from N & section line  
1950 feet from W & section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6234

Lease Name Fisher Well # 2

Operator: Petroleum Production Management, Inc.  
Name & Address: 209 E. William, Ste. 200  
Wichita, KS 67202

County Comanche 163.90  
Well Total Depth 5043 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 508

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 22 Month: 8 Year: 1995

Plugging proposal received from David

(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

Work: 5 1/2" at 5000' w/300 sx cement, Open hole 5000-5043'

1st plug sand back to 4900' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 150 sx cement.

STATE CORPORATION COMMISSION  
RECEIVED  
AUG 28 1995  
CONSULTANT  
WICHITA, KANSAS

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30 p.m. Day: 22 Month: 8 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4900' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls and 10 sx gel-blew a hole in the surface pipe.

Ran tubing to 527', could not pump or drill through a bridge.

3rd plug spotted 50 sx cement at 527',

4th plug pulled tubing to 62' and circulated cement with 15 sx.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3000' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 9-6-95

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 43417