

10-25

To: 061153
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,730-00-00
SW NW NW, SEC. 3, T 31 S, R 17 W
4290 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 8565
Operator: Huey P. Grey
Name & Address: Route 1, Box 47
Greensburg, KS 67124

Lease Name Haltom Well # 1-A
County Comanche 175.50
Well Total Depth 5400 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 301

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893
Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 10:30 a.m. Day: 25 Month: 10 Year: 19 88

Plugging proposal received from Huey P. Grey
(company name) Huey P. Grey (phone) 316-723-3123

were: 5 1/2" at 5380' Perfs at 4848-50'
1st plug sand back to 50' above perfs with 4 sx cement on top through dump bailer,
2nd plug pump 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug
and pump 100 sx cement

RECEIVED
STATE CORPORATION COMMISSION

OCT 27 1988

Plugging Proposal Received by Dick Kapp (TECHNICIAN)

Plugging Operations Observed by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 25 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4800' and dump 4 sx cement on top of sand through bailer.
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 475 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 4370' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (and/or my agent) observe this plugging.

Signed Paul A. Luthie (TECHNICIAN)

DATE 10-31-88
INV. NO. 22848