

1 080528

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,788-~~0000~~
NE NE, SEC. 18, T 34 S, R 12 (W/E)
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123
Operator: Pickrell Drilling Company
Name & Address: 110 N. Market, Suite 205
Wichita, KS 67202

Lease Name Cook "E" Well # 1
County Barber 156.29
Well Total Depth 4809 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 285

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address 107 W. Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:00 am Day: 14 Month: May Year: 19 86

Plugging proposal received from Jack Gurley
(company name) Pickrell (phone) 316-262-8427

were: 4 1/2" at 4808' PBT 4751' Perfs at 4714-4722'

1st plug pump 1 sack hulls and 20 sx cement to bottom
2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 am Day: 14 Month: May Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 3 sx hulls and 30 sx cement to bottom and stopped
plug at 3943', 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10
sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 110 sx cement, released
8 5/8" rubber plug and pumped an additional 20 sx cement.

Maximum pressure 500 psi and shut in 100 psi

Remarks: Recovered 3669' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
MAY 27 1986
5-27-86
CONSERVATION DIVISION
Wichita, Kansas

INVOLVED
MAY 28 1986

Signed J. A. [Signature]
(TECHNICIAN)

DATE _____
INV. NO. 13995