

1090238

15-007-01295-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 10-27-55

NW SE NE , SEC. 19 ; T 34 S, R 12 W/EX
3630 feet from ~~XXX~~ SE Corner of
990 feet from ~~W/EX~~ SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8873

Lease Name R. B. Cook Well # 1

Operator: Santa Fe Minerals

County Barber

Name & Address P. O. Box 1287

Well Total Depth 4880 158.60 feet

El Reno, OK 73036

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Jerry Duncan, Inc. License Number 8733

Address P. O. Box 389, Enid, OK 73702

Company to plug at: Hour: 8:00 am Day: 2 Month: October Year: 19 84

Plugging proposal received from Mike Moore

(company name) Jerry Duncan (phone) 405-237-6152

were: 5 1/2" set at 4874 PBT 4874 Perfs at 4776-4819'

1st plug pump 35 sx cement to bottom

2nd plug at 510' with 70 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by R. B. Farlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:00 am Day: 2 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 4874' PBT 4874' Perfs at 4776-4819'

1st plug pumped 35 sx cement to bottom, 2nd plug at 510' with 70 sx cement, 3rd & 4th

plugs - solid bridge- hulls - plug at 40' -- cement to surface with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 09 1984

10-9-84

CONSERVATION DIVISION

Remarks: Recovered 3198' of 5 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by W. Duncan
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 10-15-84

Signed R. B. Farlow
(TECHNICIAN)

INV. NO. 4293