

1050355

15-007-81296-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 3-10-56

NW, SEC. 19 T 34 S, R 12 W/E
~~4290~~ 1650N ~~XXXX~~ SE Corner of
feet from ~~XXXX~~ section line
~~4290~~ 3630E ~~XXXX~~ SE Corner of
feet from ~~XXXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8873

Lease Name R. B. Cook Well # 2

Operator: Santa Fe Minerals

County Barber

Name & Address P. O. Box 1287

Well Total Depth 4900 159.25 feet

El Reno, OK 73036

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 277

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Jerry Dunkin, Inc. License Number 8733

Address P. O. Box 389, Enid, OK 73702

Company to plug at: Hour: 10:00 am Day: 8 Month: October Year: 19 84

Plugging proposal received from Mike Moore

(company name) Jerry Dunkin (phone) 405-237-6152

were: 5 1/2" set at 4900' PBD 4868' Perfs at 4776-93'

1st plug pump 35 sx cement to bottom

2nd plug at 510' with 70 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: noon Day: 8 Month: October Year: 1984

ACTUAL PLUGGING REPORT 5 1/2" set at 4900' PBD 4868' Perfs at 4776-93'

1st plug pumped 35 sx cement to bottom, 2nd plug at 510' with 70 sx cement, 3rd & 4th
plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1984

10-12-84
CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Dunkin
(if additional description is necessary, use BACK of this form.) 2 Kansas

INVOICED

DATE 10-15-84

INV. NO. 4292

Signed Richard W. Lacey SR
(TECHNICIAN)