

To: 1 041266 9-12 API NUMBER 15-007-20,747-000

STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION App. NW SE SE, SEC. 23, T 34 S, R 12 W/E

130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License / 6006
Lease Name Etta Well / 1

Operator: Molz Oil Company
County Barber 154.38

Name: RR 2, Box 54
Well Total Depth 4750 feet

Address: Kiowa, KS 67070
Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 267

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 1:45 p.m. Day: 12 Month: 9 Year: 19 97

Plugging proposal received from Alan Vratil
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4740' w/150 sx cement, Perfs at 4670-98'

1st plug sand back to 4600' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION
9-17-97
SEP 17 1997

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN) DIVISION WICHITA, KS

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:30 p.m. Day: 12 Month: 9 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4520' and dumped 4 sx cement on top of

sand bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls and 125 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3700' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 9-23-97
INV. NO. 4908

Signed Stephen J. Pfeifer
(TECHNICIAN)