

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6006

Operator: Molz Oil Company

Name & Address Rt 2, Box 54

Kiowa, KS 67070

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11:45 a.m. Day: 8 Month: 2 Year: 19 91

Plugging proposal received from Ron Molz

(company name) Molz Oil Company (phone) 316-825-4338

were: 4 1/2" at 4779' w/125 sx cement, Perfs at 4690-4734'

1st plug sand back to 4640' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 8 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4640' and dumped 4 sx cement on top of sand bridge through bailer.

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 125 sx cement.

Maximum pressure 350 psi and shut in 200 psi.

Surface pipe plated with 4 1/2" collar to pump through.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3160' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-27-91

INV. NO. 30920

Signed Steve Pfeifer
(TECHNICIAN)

2-8
15-007-20830-0000 102
Drill Completion Date 11/14/79 R

API NUMBER 15-
SW SE NE, SEC. 23, T. 34 S, R. 12 W & E
2970 feet from S section line
990 feet from E section line
Lease Name Etta Well # B-1
County Barber 155.35
Well Total Depth 4780 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 314

STATE OF KANSAS
RECEIVED
FEB 13 1991
2-13-91