

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-125-20682-00-00

Spot: SWSENE

Sec/Twnshp/Rge: 7-34S-14E

3986 feet from S Section Line, 639 feet from E Section Line

Lease Name: PETERSON A

Well #: G-122

County: MONTGOMERY

Total Vertical Depth: 709 feet

Operator License No.: 35005 •

Op Name: BPG CAPITAL, LLC

Address: 100 N. COLLEGE ST., SUITE 408  
WAXAHACHIE, TX 75165

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.375	709		0 SX
SURF	6.25	22		0 SX

Well Type: EOR

UIC Docket No: E09034.78

Date/Time to Plug: 01/30/2014 12:00 AM

Plug Co. License No.: 31696

Plug Co. Name: CUNNINGHAM CRUDE, A GENERAL PARTNERSHIP

Proposal Rcvd. from: RON CUNNINGHAM

Company:

Phone: (620) 330-2724

Proposed Plugging Method: Run 1" to bottom, circulate cement to surface, pull 1" out, top off cement

Plugging Proposal Received By: DUANE SIMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 01/30/2014 12:00 PM

KCC Agent: DUANE SIMS

**Actual Plugging Report:**

Washed 1" to 675' and circulated cement to surface. Pulled 1" and topped well off. Washed 1" down backside to 75' and circulated cement to surface. Pulled 1" and topped backside off. A total of 22 sacks of cement were used to plug this well.

**Perfs:**

Top	Bot	Thru	Comments
666	679		
RECEIVED			
FEB 06 2014			
KCC Chanute Dist. #3			
DS RECEIVED KANSAS CORPORATION COMMISSION			
FEB 10 2014			
CONSERVATION DIVISION WICHITA KS			

Remarks: WELL WAS PLUGGED DUE TO FAILED MIT

Plugged through: TBG

District: 03

Signed

(TECHNICIAN)