

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-125-01932-00-00  
Spot: NWSWNWNE Sec/Twnshp/Rge: 7-34S-14E  
4357 feet from S Section Line, 2491 feet from E Section Line  
Lease Name: PETERSON A Well #: W-2  
County: MONTGOMERY Total Vertical Depth: 690 feet

Operator License No.: 35005  
Op Name: BPG CAPITAL, LLC  
Address: 100 N. COLLEGE ST., SUITE 408  
WAXAHACHIE, TX 75165

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.375	675		0 SX
SURF	6.25	20		0 SX

Well Type: EOR UIC Docket No: E09034.74 Date/Time to Plug: 01/27/2014 12:00 AM  
Plug Co. License No.: 31696 Plug Co. Name: CUNNINGHAM CRUDE, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: RON CUNNINGHAM Company: Phone: (620) 330-2724

Proposed Plugging Method: Run 1" to bottom, circulate cement to surface, pull 1" out, top off cement

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/28/2014 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Washed 1" to 625' and circulated cement to surface. Pulled 1" and topped well off. Washed down backside of casing to 225' and pumped 33 sacks of cement. Could not get a return of cement. Pulled 1" out. Ran 1" back into 225' on backside of casing next day and circulated cement to surface. Pulled 1" and topped well off. A total of 78 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
675	690		

RECEIVED  
FEB 06 2014  
KCC Chanute Dist. #3  
DS

KCC WICHITA  
FEB 10 2014  
RECEIVED

Remarks: WELL WAS PLUGGED DUE TO FAILED MIT

Plugged through: TBG

District: 03

Signed [Signature]  
6/28/14 (TECHNICIAN)  
cc to UIC 2/13/14