

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-30005-00-00
Spot: NESENE Sec/Twnshp/Rge: 13-9S-19W
3630 feet from S Section Line, 330 feet from E Section Line
Lease Name: HILGERS Well #: 2-13
County: ROOKS Total Vertical Depth: 3521 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3250		
PROD	4.5	3516		150 SX
SURF	8.625	208		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/27/2014 9:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Open Hole Arbuckle 3516' - 3521'
Casing leaks from 30' - 1950'
CIBP-3250'

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/27/2014 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3201' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 1869' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 521' and pumped 60 sx cement to circulate cement to surface. Also brought cement to surface out of 8 5/8" x 4 1/2" annulus. Pulled all tubing. Hooked to 4 1/2" casing and pumped 20 sx cement. Shut in pressure 400 psi on 4 1/2" casing and 8 5/8" x 4 1/2" annulus.

Perfs:

Top	Bot	Thru	Comments
3516	3521		

KCC WICHITA

Remarks: SWIFT SERVICES TICKET # 25280

FEB 19 2014

Plugged through: TBG

RECEIVED

District: 04

Signed Pat Bedore
02/28/14 (TECHNICIAN) CM

JAN 31 2014