

To: ✓ 1 040658  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

S-15 API NUMBER 15- 033-20,102-00-00 134

C SE SE, SEC. 18, T. 31 S, R. 17 WR  
660 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5178

Lease Name Huff Well # 1

Operator: Sidwell Oil & Gas, Inc.

County Comanche

Name & Address P.O. Box 2475

Well Total Depth 4989 162.14 feet

Pampa, TX 79065

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 521

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Greensburg Well Service License Number 5114

Address P.O. Box 632, Greensburg, KS 67054-0632

Company to plug at: Hour: 11 a.m. Day: 15 Month: 5 Year: 1992

Plugging proposal received from Carl Schield

(company name) Greensburg Well Service (phone) 316-723-2204

were: 4 1/2" at 4992' w/200 sx cement, PBD 4979', Perfs at 4952-82'

1st plug sand back to 4700' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 150  
sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12 p.m. Day: 15 Month: 5 Year: 1992

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 4 sx cement on top of  
sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, and 150 sx cement.

Maximum pressure 500 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2419' of 4 1/2" casing  
(if additional description is necessary, use BACK of this form)

Observe this plugging.

DATE 6-3-92

Signed Stephen J. P. [Signature]  
(TECHNICIAN)

INV. NO. 35375

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 19 1992  
CONSERVATION DIVISION  
Wichita, Kansas