

To: **1 051734** **11-1**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER **15-** 033-20,238-40-00

**TECHNICIAN'S PLUGGING REPORT**

Operator License # 5152  
Operator: Lee Banks, D/B/A Banks Oil Company  
Name & Address: 200 W. Douglas, Ste. 550  
Wichita, KS 67202

C SW SE, SEC. 18, T 7 S, R 17 W/E  
660 feet from S section line  
1980 feet from E section line  
Lease Name Booth Well # 1  
County Comanche  
Well Total Depth 4970 <sup>161.52</sup> feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 546

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Greensburg Well Service License Number \_\_\_\_\_  
Address 303 E. Kansas, Greensburg, KS 67054

Company to plug at: Hour: 2:30 p.m. Day: 1 Month: 11 Year: 19 93

Plugging proposal received from Carl Shield  
(company name) Greensburg Well Service (phone) 316-723-2204

Wells: 4 1/2" at 4970' w/125 sx cement, PBTD 4959', Perfs at 4943-47.5'  
1st plug sand back to 4890' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper  
plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 4 p.m. Day: 1 Month: 11 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4890' and dumped 4 sx cement on top of sand  
through bailer,  
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls, released 8 5/8" wiper plug and pumped 150 sx cement.  
Maximum pressure 400 psi and shut in 250 psi.

Remarks: Used 60/40 Poxmix 6% gel by Allied. Recovered 2500' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)  
observe this plugging.

**INVOICED**  
DATE NOV 16 1993  
INV. NO. 39189

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 03 1993  
CONSERVATION DIVISION  
Wichita, Kansas  
FORM CP-2  
Rev. 01-