

To: ✓ 1051771
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-5-94 API NUMBER 15-033-20,034-00-00

E/2 NW SW, SEC. 19, T. 7 S, R. 17
1980 feet from S section 11
965 feet from WXX section 11

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name:
Address P.O. Box 351
Liberal, KS 67905-0351

Lease Name Wilmore "A" Well # 1
County Comanche
Well Total Depth 5157 167.60 ft
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1017

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 2 p.m. Day: 5 Month: 1 Year: 19 94
Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

logs: 4 1/2" at 5155' w/150 sx cement, PBTD 5006', Perfs at 4878-88'
1st plug pump 25 sx cement and 2 sx hulls over perfs,
2nd plug pump 50 sx cement at 1017',
3rd plug pump 40 sx cement at 500',
4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____
Operations Completed: Hour: 3:30 p.m. Day: 5 Month: 1 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx cement and 2 sx hulls to 4800',
Spotted plugs through casing:
2nd plug at 1070' with 50 sx cement,
3rd plug at 500' with 40 sx cement,
4th plug at 40' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 07 1994

Remarks: Used common cement by Sargent's. Recovered 2867' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form)
Observe this plugging.

INVOICED

DATE 1-19-94
CMT. NO. 39733
1-5

Signed Richard M. Lacy
TECHNICAL STAFF