

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-20800-00-00  
Spot: NENE Sec/Twnshp/Rge: 21-31S-17W  
4720 feet from S Section Line, 760 feet from E Section Line  
Lease/Unit Name: PEPPARD Well Number: 2-21  
County: COMANCHE Total Vertical Depth: 5050 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS, INC. OF KANSAS  
Address: PO BOX 8647  
WICHITA, KS 67208

Production Casing Size: 4.5 feet: 5028 WITH 125 SX CMT  
Surface Casing Size: 8.625 feet: 611 WITH 300 SX CMT

#164<sup>13</sup>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/15/2003 1:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE MAAS Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4900' WITH 4 SX CMT. PLUG AT 1050' WITH 10 SX GEL & 50 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/15/2003 2:15 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 4939'. PERFS AT 4959-80'. SAND TO 4900' WITH 4 SX CMT ON TOP. 1ST PLUG PUMP 10 SX GEL & 50 SX CMT AT 1050'. 2ND PLUG PULL TO 630' & SPOT 50 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT.

RECEIVED  
SEP 17 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICE. RECOVERED 2830' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

*Steve Middleton*  
(TECHNICIAN)

INVOICE  
DATE 9-17-03  
INV. NO. 2004010520

Form CB-23  
*[Signature]*