

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20799-00-00
Spot: N2SW Sec/Twnshp/Rge: 22-31S-17W
2030 feet from S Section Line, 3135 feet from E Section Line
Lease/Unit Name: PEPPARD Well Number: 1-22
County: COMANCHE Total Vertical Depth: 5081 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: PO BOX 8647
WICHITA, KS 67208

Production Casing Size: 4.5 feet: 5081 WITH 150 SX CMT
Surface Casing Size: 8.625 feet: 642 WITH 300 SX CMT

#165¹³

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/17/2003 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Plugging Method: SAND TO 4900' WITH 4 SX CMT. PLUG AT 1050' WITH 10 SX GEL & 50 SX CMT. PLUG AT 670' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/17/2003 2:40 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 5013'. PERFS AT 4964-67'. SAND TO 4900' WITH 4 SX CMT. 1ST PLUG PUMP 10 SX GEL & 50 SX CMT AT 1050'. 2ND PLUG PULL TO 670' & PUMP 50 SX CMT. 3RD PLUG PULL TO 40' & PUMP 10 SX CMT.

RECEIVED
SEP 22 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2600' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

[Signature]

(TECHNICIAN)

INVOICE

DATE 9.22.03

INV. NO. 2004060530

Form CP-213