

1 051001

2-4-88

033

API NUMBER 15- ~~032~~-20,653-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

E/2 E/2 NW NWSEC. 29, T 31 S, R 17 W/E

4620 feet from S section line

4010 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Moberley "A" Well # 1

Operator: TXO Production Corporation

County Comanche 165.75

Name & Address 155 North Market, Suite 1000

Well Total Depth 5100 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 516

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 12:50 p.m. Day: 4 Month: 2 Year: 19 88

Plugging proposal received from Jerry Collins

(company name) TXO Production Corporation (phone) 316-886-5605

were: 4 1/2" at 5099' PBD 4960' Perfs at 4981-87, 4967-76'

1st plug sand back to 4830' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 4 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4830' and dumped 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 125 sx cement.

STATE CORPORATION COMMISSION

FEB 09 1988

Maximum pressure 600 psi and shut in 150 psi.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3100' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 2-10-88

Signed Richard W. Lacy (TECHNICIAN)

INV. NO. 19815