

1 050668

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-033-20,687-4-00

w/2 E/2SE SEC. 33, T. 31 S, R. 17 W/8

1320 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name L G K A Well # 1

Operator: TXO Production Corp

County Commanche 168.35

Name & Address 155 N. Market

Well Total Depth 5180 Miss feet

Suite 1000

Conductor Pipe: Size feet

Wichita, KS 67202

Surface Casing: Size 8 5/8 feet 626

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor FWA Drilling Co. Inc License Number 6165

Address Fidelity Union Twr Dallas TX

Company to plug at: Hour: 3:00am Day: 6 Month: November Year: 1985

Plugging proposal received from Allen Dick

(company name) TXO Production Corp (phone) 316-269-7600

were: Were to fill hole with heavy mud + spot plugs

through drill pipe. 1st plug @ the base of the Anhydrite

w/40sx, 2nd plug @ 630' w/40sx of cement.

3rd plug @ 40' w/solid bridge plug + 10sx of

cement Circulate Rathole + Mousehole with

10sx each Plugging Proposal Received by Richard W. Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:45am Day: 6 Month: November Year: 1985

ACTUAL PLUGGING REPORT Filled hole with heavy mud + spotted plugs

through drill pipe. 1st plug @ 1250' w/40sx

2nd plug @ 630' w/40sx

3rd plug @ 40' w/SBP + 10sx

Circulated rathole + mousehole with 10sx each

Anhydrite @ 1240 Elevation: 2067 GL

Remarks: B.J. Titan pumped 60/40 pozmix 6% gel cement

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-9-85

INV. NO. 11348

RECEIVED STATE CORPORATION COMMISSION

NOV 14 1985

DEC 16 1985 CONSERVATION DIVISION

Signed Richard W. Lacey (TECHNICIAN)