

1 050794

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,685-00-00

NW SW SE, SEC. 34, T 31 S, R 17 W/E

1220 feet from S section line

2130 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name LGK Well # 1

Operator: TXO Production Corp.
Name & Address: 155 N. Market, Suite 1000
Wichita, KS 67202

County Comanche 168.19

Well Total Depth 5175 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 639

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Oilfield Services License Number 5105

Address 107 W. Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:00 pm Day: 10 Month: April Year: 19 86

Plugging proposal received from Robbie Roberson

(company name) TXO (phone) 316-269-7600

were: 4 1/2" at 5174' PBDT 5153' Perfs at 5056-64'

1st plug sand back to 5000' and pump 4 sx cement

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 120 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:40 pm Day: 10 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 5000' and pumped 4 sx cement on top of sand.

2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

released 8 5/8" rubber plug and pumped 120 sx cement.

Maximum pressure 500 psi and shut in 250 psi

Remarks: Recovered 3300' 4 1/2" casing. Used 60/40 Pozmix 6% gel by BJ-Titan
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging. STATE CORPORATION COMMISSION

INVOICED

Signed Richard W. Lacey (TECHNICIAN)

APR 15 1986

DATE APR 15 1986

CONSERVATION DIVISION Wichita, Kansas MAY 28 1986

FORM CP-2/3 Rev.01-84