

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-22655-00-00
Spot: W2SWSWSE Sec/Twnshp/Rge: 25-31S-4W
330 feet from S Section Line, 2421 feet from E Section Line
Lease Name: HEIMERMAN FARMS 3104 Well #: 25-1
County: SUMNER Total Vertical Depth: 5125 feet

Operator License No.: 34574
Op Name: SHELL GULF OF MEXICO INC.
Address: 150 N DAIRY-ASHFORD (77079) PO BO
HOUSTON, TX 77001

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	18	60	5	36 SX
II	7	4616		1000 sx cement
PKR		4570		
PROD	7	4618	5	1135 SX
SURF	9.625	389	5	250 SX
T1	4.5	4583		

Well Type: SWD UIC Docket No: D31374.0 Date/Time to Plug: 06/08/2013 12:00 AM
Plug Co. License No.: 34896 Plug Co. Name: BAKER HUGHES OILFIELD OPERATIONS, INC.
Proposal Rcvd. from: BRITTANY NILES Company: Phone: (281) 506-1446

Proposed Plugging Method: PROPOSED METHOD OF PLUGGING: 1. SET CAST IRON BRIDGE PLUG (CIBP) IN 7" CASING AT 4,590 AT THE TOP OF ARBUCKLE FORMATION. TOP WITH 60' CLASS H CEMENT, TO 4,530'. 2. FILL WITH 9.5 LB/GAL WBM TO 300' MD. 3. SET CIBP IN 7" CASING AT 300' MD, 50' BELOW THE DEEPEST WATER WELL IN THE COUNTY. 4. FILL WITH CEMENT TO 5' BELOW GROUND LEVEL. 5. CUT CASING 5' BELOW GROUND, CAP AND WEEP HOLE. NOTE: SURFACE AND INTERMEDIATE CASING CEMENTED TO SURFACE.

Plugging Proposal Received By: KEN SCOFIELD Witness Type: PARTIAL
Date/Time Plugging Completed: 07/16/2013 12:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

Perfs:

1. SET CAST IRON BRIDGE PLUG (CIBP) IN 7" CASING AT 4,590' AT THE TOP OF ARBUCKLE FORMATION. TOP WITH 263' CLASS H CEMENT TO 4,327'. 2. FILL WITH 9.5 LB/GAL WBM TO 360' MD. 3. SET CIBP IN 7" CASING AT 360' MD, 50' BELOW THE DEEPEST WATER WELL IN THE COUNTY. 4. FILL WITH CEMENT TO 5' BELOW GROUND LEVEL. 5. CUT CASING 5' BELOW GROUND, CAP WITH WEEP HOLE (7/16/13).

Remarks: BAKER HUGHES

Plugged through: CSG

KCC WICHITA
FEB 19 2014
RECEIVED

District: 02

Signed Jonathan Hill
(TECHNICIAN)
cc to UIC 02/20/14
3/11/14
JK