

*\* OK TO INV. AS PLUS DT'S. ON/IN 5 YR.*  
 API Well Number: 15-003-02218-00-00 *BILLING CUTOFF.*  
 Spot: NWNWSWNE Sec/Twnshp/Rge: 13-21S-20E  
3833 feet from S Section Line, 2521 feet from E Section Line  
 Lease Name: EWING B Well #: X-14X  
 County: ANDERSON Total Vertical Depth: 660 feet

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGIN  
 130 SOUTH MARKET, SUITE 2078  
 WICHITA, KANSAS 67202

Operator License No.: 34170  
 Op Name: SIRIUS ENERGY CORP.  
 Address: 526 COUNTRY PL. SOUTH  
ABILENE, TX 79606

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	600		0 SX
SURF	12	20		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/16/2012 12:00 AM  
 Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
 Proposal Revd. from: RANDY TETER Company: \_\_\_\_\_ Phone: (785) 448-8571

Proposed Plugging Method: Run 3/4 inch pipe approx. 660 feet and fill 2 inch pipe with approx. 20 sacks. Run 1 inch pipe to bottom and fill backside to surface with approx. 100 sacks.

Plugging Proposal Received By: RUSSELL HINE Witness Type: NONE  
 Date/Time Plugging Completed: 08/16/2012 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:  
 RUN 3/4 INCH INSIDE 2 INCH CASING TO 630 FEET AND FILL WITH 8 SACKS OF PORTLAND CEMENT TO SURFACE. RUN 1 INCH OUTSIDE TO 250 FEET AND PUMP 90 SACKS OF CEMENT. PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 98 SACKS OF CEMENT.

Perfs:  
 RECEIVED  
 FEB 19 2014  
 KCC Chanute Dist. #3  
 LS

Remarks:  
 Plugged through: TBG

District: 03

Signed *[Signature]*  
 3/11/14

(TECHNICIAN)  
 KCC WICHITA  
 FEB 21 2014  
 RECEIVED