

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-02345-00-00

Spot: SESWSWNW

Sec/Twnshp/Rge: 4-21S-21E

2893 feet from S Section Line, 4895 feet from E Section Line

Lease Name: ROSELL

Well #: 6X

County: ANDERSON

Total Vertical Depth: 600 feet

Operator License No.: 34170

Op Name: SIRIUS ENERGY CORP.

Address: 526 COUNTRY PL, SOUTH
ABILENE, TX 79606

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|------|------------|-------------|---------|
|--------|------|------------|-------------|---------|

| | | | | |
|------|---|-----|--|------|
| PROD | 2 | 600 | | 0 SX |
|------|---|-----|--|------|

| | | | | |
|------|----|----|--|------|
| SURF | 12 | 20 | | 0 SX |
|------|----|----|--|------|

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/04/2013 12:00 AM

Plug Co. License No.: 33749

Plug Co. Name: KEPLEY WELL SERVICE, LLC

Proposal Rcvd. from: RANDY TETER

Company:

Phone: (785) 448-8571

Proposed Plugging Method: Run 3/4 inch pipe approx. 600 feet and fill 2 inch pipe with approx. 20 sacks. Run 1 inch pipe to bottom and fill backside to surface with approx. 100 sacks.

Plugging Proposal Received By: JOHN ALMOND

WitnessType: NONE

Date/Time Plugging Completed: 11/04/2013 12:00 AM

KCC Agent: LEVI SHORT

Actual Plugging Report:

Perfs:

RUN 3/4 INCH INSIDE 2 INCH CASING TO 585 FEET AND FILL WITH 6 SACKS OF PORTLAND CEMENT TO SURFACE. RUN 1 INCH OUTSIDE TO BOTTOM AND PUMP 114 SACKS OF CEMENT. PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 120 SACKS OF CEMENT. PLUG DID NOT HOLD. CONTRACTOR DRILLED CEMENT BACK TO 250 FEET AND SET PACKER. FILL WELL TO SURFACE FROM 250 FEET THEN SET J-SLOT PACKER AT 25 FEET AND SQUEEZE PLUG CEMENT.

RECEIVED

FEB 19 2014

KCC Chanute Dist. #3

LS

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]
3/11/14

(TECHNICIAN)

KCC WICHITA

FEB 21 2014

RECEIVED