

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22079-00-00
Spot: E2NWNE Sec/Twnshp/Rge: 34-8S-23W
4620 feet from S Section Line, 1650 feet from E Section Line
Lease Name: CASSEL Well #: 1
County: GRAHAM Total Vertical Depth: 3830 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: 234 W 11TH STE A PO BOX 70
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3830		175 SX
SURF	8.625	248		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/18/2014 11:30 AM
Plug Co. License No.: 33868 Plug Co. Name: RENEGADE WELL SERVICE, LLC
Proposal Rcvd. from: CURTIS R LONGPINE Company: RENEGADE WELL SERVICE, LLC Phone: (785) 625-0020

Proposed Shot perforations at 250', 1100', 1925' and 2500'.
Plugging Perforations at 3695' - 3794'.
Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/18/2014 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3650' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 2300' and pumped 150 sx cement. Good circulation of cement. Pulled tubing out. Topped off w/40 sx. Hole standing full. Tied on to back side and squeezed w/10 sx cement. Shut in pressure 400 psi.

Perfs:

Top	Bot	Thru	Comments
3734	3736		
3716	3718		
3695	3734		
3694	3696		

Remarks: QUALITY OILWELL TICKET # 483

Plugged through: TBG

KCC WICHITA

MAR 27 2014

RECEIVED

District: 04

Signed *Marvin Mills*
4/02/14 (TECHNICIAN)

CM

MAR 19 2014