

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22671-00-00
Spot: S2S2N2 Sec/Twnshp/Rge: 11-14S-15W
2310 feet from N Section Line, 2640 feet from W Section Line
Lease Name: DUMLER Well #: 20
County: RUSSELL Total Vertical Depth: 3270 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATIO
Address: 7060 S YALE # 702
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3269		200 SX
SURF	8.625	638		275 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/14/2014 8:00 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELLL SERVICE, INC.
Proposal Rcvd. from: JOHN MICKLE Company: EAGLE RIVER ENERGY CORP. Phone: (620) 282-9034

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/14/2014 11:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

03/07/2014-Moved in and started to drill down and clean out casing to produces. Had trouble getting down to 525' w/rods and tubing in well. Ran in with wash over pipe, mills and bits.
03/14/2014-Ran tubing to 430' and stacked out. Pulled up to 420' and pumped 150 sx cement w/50 # hulls. Cement circulated out both braden head and back side. POOH. Hooked to casing and pumped 100 sx cement. Closed braden head and pumped cement until pressure off 600 psi was achieved. Shut in.

GPS: 38.84993 -098.95665

Perfs:

Top	Bot	Thru	Comments
3258	3260		
3012	3199		
2911	2923		
2734	2738		

KCC WICHITA

Remarks: ALLIED CEMENTING TICKET # 627047

MAR 27 2014

Plugged through: TBG

RECEIVED

District: 04

Signed

Ray Dinkel
4/02/14

(TECHNICIAN)

CM

MAR 19 2014