

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00612-00-00
Spot: SESESWNW Sec/Twnshp/Rge: 19-12S-17W
2929 feet from S Section Line, 4233 feet from E Section Line
Lease Name: KRANNAWITTER Well #: 1
County: ELLIS Total Vertical Depth: 3688 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: 114 NORTH MAIN P.O. BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3674		175 SX
SURF	8.625	189		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/26/2014 8:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: DAVE HEIN Company: GRADY BOLDING CORP Phone: (785) 623-2084

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Tubing parted in well around 1400'. Rods parted 25' above tubing. Worked on removing for 2 days. Rods cork screwed.
Couldn't get on them.
Arb-3672' - 3688'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/26/2014 12:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Perf Tech perforated at 800' and 200'.
Professional pulling ran in hole with tubing to 1044'. Quality rigged to tubing and pumped 95 sx cement to circulate cement to surface. Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 260 sx cement w/300 # hulls mixed in to pressure with 500 psi and 200 psi shut in pressure. Rigged to 8 5/8" casing and pumped 5 sx cement to pressure with 100 psi and 100 psi shut in pressure.


GPS: 38.99529 -099.25688
3001' FSL 4170' FEL
NE SE SW NW

Remarks: QUALITY OILWELL CEMENTING TICKET # 7184

Plugged through: TBG

KCC WICHITA
APR 01 2014
RECEIVED

District: 04

Signed  (TECHNICIAN)
4/02/14

CM

MAR 27 2014