

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10296-00-00
Spot: SENW Sec/Twnshp/Rge: 9-33S-41W
1980 feet from N Section Line, 1980 feet from W Section Line
Lease Name: BERRYMAN RICHFIELD UNIT Well #: 18-1
County: MORTON Total Vertical Depth: 5147 feet

Operator License No.: 34832
Op Name: SCOUT ENERGY MANAGEMENT LLC
Address: 14400 MIDWAY RD
DALLAS, TX 75244

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1500		
CIBP		4900		WITH 10 SX CMT
PROD 4.5		5147	0	WITH 200 SX CMT
SURF 8.625		1497		WITH 625 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/26/2014 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: 1. MIRUSU UNFLAGED NU BOP. SPOT 2 3/8 WORK STRING. PU ON/OFF TOOL OVERSHOT & TIH. LATCH CASING PATCH, RELEASE AS-1X PACKER & POH & LAY DOWN CASING PATCH & 92 JOINTS 2 3/8 TUBING. 2. TIH W/ TUBING AT 4900, CIRCULATE HOLE W/ MUD & SPOT 10 SACKS CEMENT ON TOP OF EXISTING RBP. POH W/ TUBING. 3. NDBOP, UNPACK 4 1/2 CASING & WELD ON 4 1/2 RAMS. WORK CASING FOR FREE POINT. CUT & PULL FREE PIPE. 4. TIH W/ TUBING AT 1530; MIX & SPOT 80 SACKS CLASS C CEMENT. PULL UP HOLE W/ TUBING AT 550; MIX & SPOT 60 SACKS OF CEMENT. POH W/ TUBING. NDBOP TOP OUT 64-4 W/ 20 SACKS CEMENT. RD MOSU. 5. CUT & CAP WELL. DUG UP RIG ANCHORS.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 02/26/2014 3:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

TOC @ 650'. CIBP @ 4900' WITH 10 SX CMT. PERFORATE @ 550'. SET CIBP @ 1500'. RELEASE & PUMP 100 SX CMT INSIDE 4 1/2". OPEN 8 5/8" & PUMP 160 SX CMT TO 0'. TOP OFF WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5035	5040		
5021	5028		

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES.

KCC WICHITA

APR 01 2014

Plugged through: TBG

RECEIVED

District: 01

RECEIVED

MAR - 6 2014

KCC DODGE CITY

Signed

[Signature]
4/04/14
(TECHNICIAN)

AM