

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10436-00-00
Spot: SWSE Sec/Twnshp/Rge: 9-33S-41W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: BERRYMAN RICHFIELD UNIT Well #: 21-2
County: MORTON Total Vertical Depth: 5100 feet

Operator License No.: 34832
Op Name: SCOUT ENERGY MANAGEMENT LLC
Address: 14400 MIDWAY RD
DALLAS, TX 75244

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5100	1716	WITH 125 SX CMT
SURF	8.625	1525		WITH 645 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/04/2014 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: 1. MIRUSU UNFLAGED NU BOP. SPOT 2 3/8 WORK STRING. 2. PICK UP OVERSHOT & TIH & LATCH CASING PATCH, RELEASE BOTTOM PACKER & POH & LAY DOWN PATCH. 3. TIH W/ OVERSHOT TO RBP AT 4090 FT. RELEASE & POH. 4. TIH W/ OPEN-ENDED TUBING & TAG FILL AT 4306, MIX & SPOT 25 SACKS OF CEMENT FOR BOTTOM PLUG. POH & WAIT ON CEMENT. TAG TOC & CIRCULATE HOLE W/ MUD. POH W/ TUBING. 5. ND BOP, UNPACK 4 1/2 CASING & WELD ON 4 1/2 PULL SUB. PULL 4 1/2 SLIPS & NU BOP W/ 4 1/2 RAMS. WORK CASING FOR FREEPOINT. CUT & PULL FREE PIPE. 6. TIH W/ TUBING & CASING STUB & SPOT 50 SACKS OF CEMENT TO COVER MULTIPLE CASING LEAKS. PULL UP HOLE AT 1575 FT. MIX & SPOT 80 SACKS OF CEMENT. PULL UP HOLE AT 550 FT. MIX & SPOT 60 SACKS OF CEMENT. POH W/ TUBING & TOP OUT 64-4 W/ 20 SACKS OF CEMENT. RD MOSU. 7. CUT & CAP WELL. DIG UP RIG ANCHORS.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 03/04/2014 5:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

TOF @ 1754'. SET 8 5/8" CEMENT RETAINER TO 1475'. PUMP 200 SX CMT AT 400 PSI. STING OUT WITH LAST 25 SX CMT ON TOP OF RETAINER. PLUG AT 550' WITH 60 SX CMT. PLUG AT 64' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5049	5054		

KCC WICHITA
APR 01 2014

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES.

RECEIVED

Plugged through: TBG

District: 01

RECEIVED
MAR - 6 2014
KCC DODGE CITY

Signed

[Signature]
4/04/14 (TECHNICIAN)

PM