

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-23642-00-00  
Spot: W2SESESE Sec/Twnshp/Rge: 29-24S-13W  
339 feet from S Section Line, 614 feet from E Section Line  
Lease Name: KBJ CATTLE CO. Well #: 1  
County: STAFFORD Total Vertical Depth: 4252 feet

Operator License No.: 5205  
Op Name: MID-CONTINENT ENERGY CORP.  
Address: 105 S BROADWAY STE 360  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4140		WITH 2 SX CMT
PROD	5.5	4250	1590	WITH 175 SX CMT
SURF	8.625	266		WITH 225 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/21/2014 4:00 PM  
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.  
Proposal Rcvd. from: JEFF BURK Company: PETERRA ENERGY SERVICES Phone: (316) 250-5655

Proposed Plugging Method: SET CIBP @ 4140' & 2 SX CMT. PLUG AT 800' WITH 12 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/21/2014 6:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4140' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 862' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 305' WITH 50 SX CMT. 3RD PLUG AT 44' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4190	4194		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

KCC WICHITA

APR 01 2014

RECEIVED

District: 01

Signed

*Stephen J. Pfeifer*  
4/04/14  
(TECHNICIAN)

RECEIVED

MAR 27 2014

KCC DODGE CITY

BAY