

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-40235-00-00
Spot: NENWSWSE Sec/Twnshp/Rge: 10-34S-12E
1050 feet from S Section Line, 1985 feet from E Section Line
Lease Name: COUNTY FARM A Well #: 4
County: CHAUTAUQUA Total Vertical Depth: 994 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.875	760		0 SX
SURF	8.25	60		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/19/2014 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface and production casing cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed: 02/20/2014 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 850' gelled hole and spotted 20 sacks of cement. Pulled 1" and perforated casing at 600' and 350'. Ran back into 600' and spotted 15 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 158 sacks of cement were used to plug this well.

Perfs:

Remarks:

Plugged through: TBG

RECEIVED
MAR 27 2014
KCC Chanute Dist. #3
DS
KCC WICHITA
MAR 31 2014
RECEIVED

District: 03

Signed [Signature]
2/20/14 (TECHNICIAN)