

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-40238-00-00
Spot: SESENWSE Sec/Twnshp/Rge: 10-34S-12E
1591 feet from S Section Line, 1509 feet from E Section Line
Lease Name: COUNTY FARM A Well #: 8
County: CHAUTAUQUA Total Vertical Depth: 940 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.875	745		0 SX
SURF	8.25	69		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/27/2014 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 02/28/2014 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1/2" down 1 1/4" to 800' gelled hole and spotted 10 sack plug. Pulled 1/2" out of casing. Tried to pull 1 1/4" out of well but couldn't. Perforated 4.5" casing at 350'. Ran 1" into 350' on backside of 1 1/4" and 1/2" down inside of 1 1/4" to 350' and circulated cement to surface. Pulled both strings of pipe out of well and topped well off. A total of 135 of cement were used to plug this well.

Perfs:

RECEIVED
MAR 27 2014
KCC Chanute Dist. #3
DS

KCC WICHITA
MAR 31 2014
RECEIVED

Remarks:
Plugged through: TBG

District: 03

Signed Duane A Sims
4/04/14 (TECHNICIAN)