

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-24017-00-00  
Spot: NESWSESE Sec/Twnshp/Rge: 17-10S-22W  
640 feet from S Section Line, 700 feet from E Section Line  
Lease Name: FRITTS TRUST Well #: 1-17  
County: GRAHAM Total Vertical Depth: 4100 feet

Operator License No.: 3882  
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN  
Address: 1515 WYNKOOP, STE 700  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	333		200 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/11/2014 12:00 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 270 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER Witness Type: NONE  
Date/Time Plugging Completed: 03/11/2014 10:30 PM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st plug @4026 w/50 sx  
2nd plug @1880 w/25 sx  
3rd plug @1005 w/100 sx  
4th plug @385 w/40 sx  
5th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

KCC WICHITA  
MAR 27 2014  
RECEIVED

District: 04

Signed Ed Schumacher  
4/04/14 (TECHNICIAN)

CM