

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24803-00-00
Spot: S2NESESW Sec/Twnshp/Rge: 6-11S-18W
900 feet from S Section Line, 2310 feet from W Section Line
Lease Name: PEAVEY Well #: 4
County: ELLIS Total Vertical Depth: 3521 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3521		250 SX
SURF	8.625	215		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/06/2014 12:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: LANCE FELLHOELTER Company: EXPRESS WELL SERVICE & SUPPL Phone: (316) 262-3596

Proposed Plugging Method: Ordered 305 sx 60/40 pozmix 4% gel cement w/500 # hulls and 6 sx gel. CIBP at 2956'
Perforations: 3001' - 3145', 3215' - 3219' and 3240' - 3462'.
Perf Tech perforated on 03/06/2014 at 1850', 1332' and 716'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/07/2014 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 2900' and pumped 6 sx gel followed by 50 sx cement w/250 # hulls. Pulled tubing to 1850' and pumped 150 sx cement. Good circulation of cement. Pulled tubing out. Topped off w/25 sx. Can not tie on to back side. Bull plug broken off in head. Cut off well on 03/08/2014. Backside full of cement according to operator.
GPS: 39.12012 -099.36211

Perfs:

Remarks: QUALITY CEMENTING TICKET # 7741
Plugged through: TBG

KCC WICHITA
MAR 27 2014
RECEIVED

District: 04

Signed *Marvin Mills*
4/04/14 (TECHNICIAN) CM

MAR 19 2014