

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-22058-00-00
Spot: SESWSNW Sec/Twnshp/Rge: 4-19S-17W
2400 feet from N Section Line, 1850 feet from W Section Line
Lease Name: JECHA 4 Well #: 1
County: RUSH Total Vertical Depth: 3851 feet

Operator License No.: 34158
Op Name: O'BRIEN RESOURCES, LLC
Address: PO BOX 6149
SHREVEPORT, LA 71136

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	259		WITH 175 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/06/2014 7:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: ANDY DINKEL Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 3806' WITH 50 SX CMT. 2ND PLUG AT 1180' WITH 50 SX CMT. 3RD PLUG AT 450' WITH 30 SX CMT. 4TH PLUG AT 290' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: PARTIAL
Date/Time Plugging Completed: 03/06/2014 11:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

1ST PLUG AT 3806' WITH 50 SX CMT. 2ND PLUG AT 1179' WITH 50 SX CMT. 3RD PLUG AT 458' WITH 30 SX CMT. 4TH PLUG AT 292' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

KCC WICHITA
MAR 10 2014
RECEIVED

District: 01

Signed Richard M. Lacey
3/24/14 (TECHNICIAN)

RECEIVED

MAR -6 2014

KCC DODGE CITY

Handwritten initials