

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-20559-00-01
Spot: NESESESE Sec/Twnshp/Rge: 10-28S-36W
465 feet from S Section Line, 113 feet from E Section Line
Lease Name: BULLOCK A Well #: 1 SWD
County: GRANT Total Vertical Depth: 4780 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4150		WITH 2 SX CMT
DVT		3315		
PROD	5.5	4779	1818	WITH 400 SX CMT
SURF	8.625	1787		WITH 900 SX CMT

Well Type: SWD UIC Docket No: Date/Time to Plug: 02/26/2014 1:30 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CIBP @ 4795' WITH 2 SX CMT. CIBP @ 4190' WITH 2 SX CMT. 25 SX CMT AT 3365'. PLUG AT 1820' WITH 50 SX CMT. PLUG AT 700' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 02/27/2014 2:00 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

CIBP @ 4150' WITH 2 SX CMT. COULDN'T GET ANY LOWER DUE TO JUNK IN THE HOLE. 1ST PLUG AT 1818' WITH 50 SX CMT. DISPLACED WITH 38 BBL MUD. 2ND PLUG AT 700' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4240	4270		
4220	4230		
4204	4220		

KCC WICHITA
MAR 10 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed Nathan Willis
(TECHNICIAN)

RECEIVED

FEB 28 2014

KCC DODGE CITY