

\*OK TO INV. AS PLUG DT'S. W/IN 5 YR. BILLING CUTOFF.

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20878-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 16-2S-27W  
4380 feet from S Section Line, 340 feet from E Section Line  
Lease Name: CHAMBERS D Well #: 2  
County: DECATUR Total Vertical Depth: 3726 feet

Operator License No.: 8981  
Op Name: ADECO, INC.  
Address: BOX 873  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3726		355 SX
SURF	8.625	222		135 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/26/2012 12:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: HAROLD BELLERIVE Company: ALLIANCE WELL SERVICE INC. Phone: (785) 635-4531

Proposed Plugging Method: Ordered 410 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE  
Date/Time Plugging Completed: 12/26/2012 12:00 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated at 2065' and 1444'. Ran in hole with tubing (open ended). Stacked out at 3400'. Pulled joint out. Pumped cement at 3385'. S.O.S. pumped 125 sacks with 250# of hulls. Pulled tubing up to 2200'. Pumped 110 sacks with 150# hulls. Pulled tubing up to 1080'. Pumped 135 sacks with 100# of hulls. Had good cement circulation to surface. Pulled out of hole with tubing. Pumped 20 sacks to top off casing. Dug out braden head. Hooked up to 8 5/8". Pumped 20 sacks. Pressured to 250#. Curculated to backside of 8 5/8".

Perfs:

Top	Bot	Thru	Comments
3458	3462		
3368	3372		
3358	3362		

Remarks: SOS  
Plugged through: TBG

District: 04

Signed Darrel Dipman (TECHNICIAN) 3/21/14 CM

KCC WICHITA

MAR 05 2014

RECEIVED

Form CP-2/3