

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-05000-00-01
Spot: SESWNE Sec/Twnshp/Rge: 33-20S-12W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: DEAN HADDON (SALING) Well #: 1-33
County: BARTON Total Vertical Depth: 3430 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3421		120 SX
SURF	8.625	280		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/12/2014 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: KEVIN WILES JR Company: AMERICAN WARRIOR INC. Phone: (620) 275-0296

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/12/2014 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

03/11/14- Sanded off bottom casing. Could not pull casing.
03/12/14- Perforated at 1500', 700' and 280'.
Ran tubing to 1550' and pumped 85 sx cement w/150 # hulls. Pulled tubing to 700' and pumped 120 sx cement. Cement circulated. POOH. Hooked to casing and pumped 50 sx cement at 250 psi. Cellar was full of cement.
GPS: 38.39352 -098.94892

Perfs:

Top	Bot	Thru	Comments
3211	3214		
3203	3205		
3180	3184		
3058	3214		

KCC WICHITA

MAR 19 2014

RECEIVED

Remarks: QUALITY WELL SERVICE TICKET # 10001

Plugged through: TBG

District: 04

Signed Ray A. Dinkel
3/20/14 (TECHNICIAN)

CM

MAR 14 2014