

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20183-00-01
Spot: SENWSWSE Sec/Twnshp/Rge: 24-5S-18W
973 feet from S Section Line, 2245 feet from E Section Line
Lease Name: BOGART B Well #: 2
County: PHILLIPS Total Vertical Depth: 3398 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3394		150 SX
SURF	8.625	108		150 SX

Well Type: EOR UIC Docket No: E24440.1 Date/Time to Plug: 02/25/2014 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DALE FERLAND Company: ALLIED CEMENT COMPANY Phone: (785) 302-1435

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforated at 950' w/750 sx cement.
Inj perforations: 3167' - 3245'

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/25/2014 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3180' and pumped 125 sx cement w/250 # hulls. Pulled tubing to 1700' and pumped 100 sx cement w/100 # hulls. Pulled all tubing. Topped off 4 1/2" casing with 15 sx cement. Visually checked 8 5/8" x 4 1/2" annulus. Cement to surface.

GPS: 39.59929N -099.29745W

Perfs:

Top	Bot	Thru	Comments
3260	3265		
3232	3236		
3214	3218		
3206	3210		
3167	3171		

Remarks: ALLIED TICKET # 54988

Plugged through: TBG

District: 04

Signed

Pat Bedore

TECHNICIAN)

CM

cc to JUC 3/20/14

KCC WICHITA

Form CP-2/3

MAR 03 2014

MAR 05 2014

RECEIVED