

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23241-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 14-19S-15W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: EBERLY Well #: 1
County: BARTON Total Vertical Depth: 3535 feet

Operator License No.: 31093
Op Name: BECKER OIL CORPORATION
Address: PO BOX 1150
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3534		275 SX
SURF	8.625	862		425 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/11/2014 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DOUG BROWN Company: BECKER OIL Phone: (620) 287-4724

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/11/2014 11:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

03/10/14- Sanded back and spotted 5 sx cement to 3152'.
03/11/14- Cut casing at 1996'.
Pulled casing to 1500' and pumped 125 sx cement w/200 # hulls. Pulled casing to 975' and pumped 50 sx cement w/100 # hulls. Pulled casing to 500' and pumped 50 sx cement w/100 # hulls. Pulled casing to 250' and pumped 100 sx cement. Cement circulated. POOH and cellar stayed full.
GPS: 38.39352 -098.94892

Perfs:

Top	Bot	Thru	Comments
3227	3378		

Remarks: COPELAND ACID AND CEMENTING TICKET # 40431

Plugged through: CSG

KCC WICHITA

MAR 19 2014

RECEIVED

District: 04

Signed Ray A. Dinkel
3/20/14 (TECHNICIAN)

CM

MAR 14 2014