

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-063-22138-00-00  
Spot: W2W2NWNE Sec/Twnshp/Rge: 9-15S-31W  
660 feet from N Section Line, 2475 feet from E Section Line  
Lease Name: T-NELSON Well #: 1-9  
County: GOVE Total Vertical Depth: 4421 feet

Operator License No.: 31120  
Op Name: PELICAN HILL OIL & GAS, INC.  
Address: 1401 N EL CAMINO REAL SUITE 207  
SAN CLEMENTE, CA 92672

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4445		175 SX
SURF	8.625	264		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/13/2014 9:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: HAROLD BELLERIVE Company: PELICAN HILLS O & G Phone: (949) 498-2101

Proposed Plugging Method: 8 5/8" surface casing set at 264' w/200 sx cement. 5 1/2" production casing set at 4445' w/175 sx cement. TD 4421'. Perforations: 4363' - 4380', 4235' - 4230', 3830' - 3961'. Port Collar at 2147' was not cemented. Well is non-commercial. Plug through tubing and casing.

Ordered 450 sx 60/40 pozmix 4% gel cement, 12 sx gel and 600 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/13/2014 7:45 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4300' and pumped 12 sx gel followed by 100 sx cement w/300 # hulls. Pulled tubing out of hole. Pulled stretch in casing to establish free point at 1210'. Perforated 5 1/2" casing at 2165'. Connected to casing and pumped 50 sx cement and displaced with 43 bbl water. Cut casing at 1215'. Casing free. Pulled one joint casing. Connected to casing and pumped 100 sx cement w/200 # hulls. Pulled casing to 315' and pumped 120 sx cement w/50 # hulls. Circulated cement to surface. Pulled casing to surface. Topped off 8 5/8" casing w/10 sx cement.

GPS: 38.77072N -100.77161W

Perfs:

Top	Bot	Thru	Comments
4363	4380		
4235	4330		
3830	3961		

KCC WICHITA  
MAR 19 2014  
RECEIVED

Remarks: ALLIANCE WELL SERVICE INC. SERVICE UNIT, GLOBAL CEMENT TICKET # 1263 PLUGGED THROUGH TUBING AND CASING

Plugged through: TBG

District: 04

Signed Darrel Dipman (TECHNICIAN)

3/24/14

CM

MAR 14 2014