

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-063-22124-00-00  
Spot: SENEWSWE Sec/Twnshp/Rge: 34-14S-31W  
905 feet from S Section Line, 1455 feet from E Section Line  
Lease Name: T-NELSON Well #: 1-34  
County: GOVE Total Vertical Depth: 4422 feet

Operator License No.: 31120  
Op Name: PELICAN HILL OIL & GAS, INC.  
Address: 1401 N EL CAMINO REAL SUITE 207  
SAN CLEMENTE, CA 92672

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4421		175 SX
SURF	8.625	263		170 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/11/2014 9:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: HAROLD BELLERIVE Company: PELICAN HILLS O & G Phone: (949) 498-2101

Proposed Plugging Method: 8 5/8" surface casing set at 263' w/180 sx cement. 5 1/2" production casing set at 4421' w/175 sx cement. TD 4422'. Perforations: 4316' - 4337', 4222' - 4226' and 3734' - 3913'. Port collar was not cemented. Well is non commercial. Plug through tubing and casing.

Ordered 450 sx 60/40 pozmix 4% gel cement, 12 sx gel and 600 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/12/2014 12:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4300' and pumped 12 sx gel followed by 100 sx cement w/300 # hulls. Pulled tubing out of hole. Pulled stretch in casing to establish free point. Estimated free point at 3000'. Shot production casing at 2742'. Could not pull casing. Shot casing at 2060' and pulled one joint of casing. Shut down for the day.  
03/12/14- 5 1/2" casing at 2030'. Connected to 5 1/2" casing and pumped 100 sx cement w/200 # hulls. Pulled casing to 315' and pumped 80 sx cement w/50 # hulls. Cement circulated to surface. Pulled casing to surface and topped off 8 5/8" casing w/40 sx cement. Plug complete.

GPS: 38.78952N -100.74964W

Perfs:

Top	Bot	Thru	Comments
4316	4337		
4222	4226		
3734	3913		

KCC WICHITA  
MAR 19 2014  
RECEIVED

Remarks: ALLIANCE WELL SERVICE UNIT, GLOBAL CEMENT COMPANY TICKET # 1261 PLUGGED THROUGH TUBING AND CASING

Plugged through: TBG

District: 04

Signed Darrel Dipman (TECHNICIAN)

3/24/14

CM

MAR 14 2014