

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22504-00-00
Spot: SWNESE Sec/Twnshp/Rge: 34-15S-14W
1653 feet from S Section Line, 1031 feet from E Section Line
Lease Name: NUSS Well #: 1
County: RUSSELL Total Vertical Depth: 3390 feet

Operator License No.: 31144
Op Name: REDDIG, BRIAN DBA REDDIG ENTERP
Address: 4325 177TH ST
GORHAM, KS 67640

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3386		160 SX
SURF	8.625	559		265 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/19/2013 9:30 AM
Plug Co. License No.: 34410 Plug Co. Name: AMERICAN PULLING SERVICE
Proposal Rcvd. from: BRIAN "DOC" REDDIG Company: REDDING ENTERPRISES Phone: (785) 445-8166

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement, 12 sx gel and 450# hulls.
Perforated: 1450'.
CP-1 reported squeezed at 400' - 900' in 2011.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/19/2013 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 3200' and pumped 12 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1500' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 500' and pumped 50 sx cement. Cement circulated. POOH. Hooked to casing and pumped 5 sx cement at 400 psi. Shut in. Braden head was dug out and found to be full of cement from earlier squeeze.

GPS: 38.70138 -098.86043

Remarks: QUALITY CEMENTING TICKET # 6588

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel
3/24/14

(TECHNICIAN)

KCC WICHITA

CM

MAR 05 2014

RECEIVED