

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-21029-00-00
Spot: S2NESE Sec/Twnshp/Rge: 19-16S-31W
1635 feet from S Section Line, 540 feet from E Section Line
Lease Name: HUSEMAN 19D Well #: 1
County: SCOTT Total Vertical Depth: 4750 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		WITH 165 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/06/2014 2:30 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Revd. from: WILLIE WYNN Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 2370' WITH 50 SX CMT. 2ND PLUG AT 1650' WITH 80 SX CMT. 3RD PLUG AT 810' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 03/06/2014 4:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 2370' WITH 50 SX CMT. 2ND PLUG AT 1650' WITH 80 SX CMT. 3RD PLUG AT 810' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

KCC WICHITA

MAR 13 2014

RECEIVED

District: 01

RECEIVED

MAR -7 2014

KCC DODGE CITY

Signed Eric MacLaren
3/24/14 (TECHNICIAN)

AMZ