

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-19017-00-01
Spot: NWSWNE Sec/Twnshp/Rge: 11-1S-27W
4324 feet from S Section Line, 1134 feet from E Section Line
Lease Name: WARNER UNIT Well #: 104-W
County: DECATUR Total Vertical Depth: 3467 feet

Operator License No.: 31660
Op Name: ROBUCK, DON E. DBA ENERGY SEARC
Address: 12101 E. 2ND AVE, STE 100
AURORA, CO 80011

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3466		600 SX
SURF	8.625	320		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/12/2014 3:30 PM
Plug Co. License No.: 31660 Plug Co. Name: ROBUCK, DON E. DBA ENERGY SEARCH OPERATING COMPANY
Proposal Rcvd. from: BRETT ROBUCK Company: ENERGY SEARCH Phone: (308) 345-7200

Proposed Plugging Method: 8 5/8" surface casing set at 320' w/250 sx cement. 5 1/2" production casing set at 3466' w/200 sx cement. Stage collar at 1920' w/400 sx cement. TD 3467', PBD 3457'. Perforations: 3225' - 3235', 3257' - 3260', 3267' - 3275', 3340' - 3343', 3345' - 3353', 3379' - 3388', 3405' - 3411' and 3419' - 3425'.

Ordered 400 sx 60/40 pozmix 4% gel cmeent, 8 sx gel and 600 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/12/2014 7:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 3217' and pumped 8 sx gel followed by 80 sx cement w/300 # hulls. Pulled tubing to 1957' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 1019' and pumped 130 sx cement w/100 # hulls. Cement circulated to surface. Pulled tubing to surface. Connected to 5 1/2" production casing and pumped 15 sx cement. Connected to 8 5/8" surface casing. Immediate pressure. Braden head ruptured.

GPS: 39.98498N -100.31261W

Perfs:

Top	Bot	Thru	Comments
3419	3425		
3405	3411		
3379	3388		
3345	3353		
3340	3343		
3267	3275		
3257	3260		
3225	3235		

Remarks: GLOBAL CEMENT COMPANY TICKET # 1262

Plugged through: TBG

KCC WICHITA

MAR 19 2014

RECEIVED

District: 04

Signed Darrel Dipman
3/24/14 (TECHNICIAN)

CM

MAR 14 2014

Form CP-2/3