

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-25524-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 21-17S-13W  
1650 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: SCHNEIDER Well #: 1  
County: BARTON Total Vertical Depth: 3521 feet

Operator License No.: 9292  
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL  
Address: 211 S FRONT ST  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3518	1585	150 SX
SURF	8.625	457		215 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/27/2014 8:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: TIM SCHECK Company: SCHECK OIL OPERATION Phone: (785) 483-4096

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/27/2014 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded of perforations and topped with cement. Cut casing at 1585'. Pulled to 1530' and pumped 125 sx cement w/200 # hulls. Lost circulation. Pulled casing to 1250' and pumped 40 sx cement w/50 # hulls. Had circulation. Pulled casing to 900' and pumped 60 sx cement w/100 # hulls. Pulled casing to 450'. Circulated cement to surface with 125 sx cement.

GPS: 38.555200 -098.764855

Perfs:

Top	Bot	Thru	Comments
3360	3361		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

KCC WICHITA

District: 04

MAR 18 2014  
RECEIVED

Signed Bruce Rodie  
3/24/14 (TECHNICIAN)

CM

MAR 06 2014