

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21779-00-00
Spot: E2SWSWNE Sec/Twnshp/Rge: 13-27S-20W
2274 feet from N Section Line, 2283 feet from E Section Line
Lease Name: C. ZIMMERMAN 'A' Well #: 1-13
County: KIOWA Total Vertical Depth: 4950 feet

Operator License No.: 33036
Op Name: STRATA EXPLORATION, INC.
Address: PO BOX 401
FAIRFIELD, IL 62837

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4771		WITH 2 SX CMT
PROD	5.5	4947	2003	WITH 200 SX CMT
SURF	8.625	608		WITH 370 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/05/2014 11:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: MICHAEL POLLY Company: STRATA EXPLORATION Phone: (719) 846-3434

Proposed Plugging Method: BP 50' ABOVE TOP PERF WITH 2 SX CMT (4771') PLUG AT 1290' WITH 10 SX GEL & 50 SX CMT. PLUG AT 640' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/05/2014 2:10 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4771' WITH 2 SX CMT. 1ST PLUG AT 1299' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 641' WITH 50 SX CMT. 3RD PLUG AT 52' WITH 20 SX CMT. CMT CIRCULATED & HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4840	4858		
4821	4825		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

KCC WICHITA

MAR 10 2014

RECEIVED

District: 01

Signed Eric McClaren (TECHNICIAN)

3/24/14

RECEIVED
MAR - 6 2014
KCC DODGE CITY

Handwritten initials