

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22156-00-00
Spot: E2E2W2 Sec/Twnshp/Rge: 19-7S-17W
2640 feet from N Section Line, 2310 feet from W Section Line
Lease Name: HUTTON Well #: 4
County: ROOKS Total Vertical Depth: 3340 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13.375	88		100 sx
PROD	5.5	3338		150 SX
SURF	8.625	1184		500 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/10/2014 2:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered 315 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Mud anchor and 1-2 joints tubing stuck at 3190'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/10/2014 5:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3180' and pumped 150 sx cement w/300 # hulls. Pulled tubing to 1540' and pumped 140 sx cement to circulate to surface. Pulled all tubing and topped off 5 1/2" casing w/25 sx cement. 8 5/8" x 5 1/2" annulus cemented to surface. Visually checked.
GPS: 39.42952N -099.26023W

Perfs:

Top	Bot	Thru	Comments
3265	3270		
3226	3246		

Remarks: ALLIED TICKET # 54995

Plugged through: TBG

KCC WICHITA

MAR 21 2014

RECEIVED

District: 04

Signed

Pat Bedore
3/24/14 (TECHNICIAN)

CM

MAR 18 2014