

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21626-00-00
Spot: NENWNW Sec/Twnshp/Rge: 9-19S-28W
337 feet from N Section Line, 1047 feet from W Section Line
Lease Name: HINEMAN Well #: 1
County: LANE Total Vertical Depth: 4650 feet

Operator License No.: 30269
Op Name: ARGENT ENERGY, INC.
Address: 1313 N WEBB RD STE 210
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		2149		WITH 325 SX CMT
PROD	4.5	4649	0	WITH 210 SX CMT
SURF	8.625	256		WITH 165 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/28/2014 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: BRAD SEIB Company: ARGENT ENERGY Phone: (785) 798-0020

Proposed Plugging Method: PUMP 30 SX CMT & 200# HULLS, THEN GEL SPACER TO 2200'. CMT TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/28/2014 10:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 50 SX CMT & 200# HULLS FOLLOWED BY 8 SX GEL, THEN 150 SX CMT. PRESSURED TO 500#. TIED ONTO BACKSIDE & PUMPED 15 SX CMT & PRESSURED TO 500#. HELD.

Perfs:

Top	Bot	Thru	Comments
4304	4306		

KCC WICHITA
APR 03 2014
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed Michael J. Maier
4/30/14 (TECHNICIAN)

RECEIVED
MAR 12 2014

KCC DODGE CITY

AGC