

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-20618-00-01
Spot: NESWSENE Sec/Twnshp/Rge: 10-17S-24W
3171 feet from S Section Line, 667 feet from E Section Line
Lease Name: STUTZ BB Well #: DO1
County: NESS Total Vertical Depth: 4590 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4000		
PROD	5.5	4570	0	WITH 100 SX CMT
SURF	8.625	218		WITH 150 SX CMT

Well Type: EOR UIC Docket No: E17208.1 Date/Time to Plug: 03/06/2014 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: NEIL PFANNENSTIEL Company: CITATION OIL & GAS Phone: (281) 891-1000

Proposed Plugging Method: Plug #1 - Mix 55 sx cmt with 300 # Hull mixed Squeeze 150 sx cmt behind pipe Plug #2 - 80 sx over casing volume

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/06/2014 3:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4433' & PUMP 55 SX CMT & 250# HULLS. PERFORATE AT 1000'. TIED ON CASING & PUMPED 220 SX CMT. DID NOT CIRCULATE. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4508	4518		
4485	4498		

KCC WICHITA

APR 03 2014

RECEIVED

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed: Michael J. Maier (TECHNICIAN)

RECEIVED

MAR 12 2014

KCC DODGE CITY

Handwritten initials