

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-25817-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 34-34S-8E
2970 feet from S Section Line, 2310 feet from E Section Line
Lease Name: MONTGOMERY Well #: 4
County: CHAUTAUQUA Total Vertical Depth: 2470 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2469		327 SX
SURF	8.625	135		50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/26/2014 12:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: ALAN NATION Company: _____ Phone: (620) 222-4304

Proposed Plugging Method: As per state instructions. NOTE: Production casing has been cemented from 550' to surface with 125 sacks of cement.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed: 02/27/2014 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" to 2215' gelled hole and spotted 40 sacks of cement. Pulled 2" and perforated casing at 1660'. Ran 2" back into 1660' and spotted 35 sacks of cement. Pulled up to 550' and circulated cement to surface with 85 sacks. Pulled 2" out and cement kept falling. They let set til next day and went back in at tagged cement at 540'. They circulated cement to surface with 50 more sacks of cement. Pulled 2" and topped well off. A total of 210 sacks of 60/40 poz mix cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
2077	2090		
2021	2026		

RECEIVED
MAR 25 2014
KCC Chanute Dist. #3
DS

Remarks: WELL WAS PLUGGED DUE TO EXPIRED 10 YEAR TA.

Plugged through: TBG

District: 03

Signed [Signature]
4/02/14 (TECHNICIAN)

KCC WICHITA Form CP-2/3

MAR 27 2014

RECEIVED