

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-20527-00-00
Spot: SENENWSE Sec/Twnshp/Rge: 10-34S-12E
2014 feet from S Section Line, 1560 feet from E Section Line
Lease Name: COUNTY FARM A Well #: 16
County: CHAUTAUQUA Total Vertical Depth: 954 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	954		25 SX
SURF	10	10		4 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/28/2014 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed: 03/01/2014 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" down backside of 4.5" to 350' and circulated cement to surface with 72 sacks of cement. Ran 1" to 850' inside 4.5" gelled hole and spotted 10 sack plug. Pulled 1" and perforated casing at 600'. Ran back into 600' and spotted 10 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 127 sacks of cement were used to plug this well.

Perfs:

Remarks:

Plugged through: TBG

RECEIVED
MAR 27 2014
KCC Chanute Dist. #3
DS
KCC WICHITA
MAR 31 2014
RECEIVED

District: 03

Signed Duane A Sims
4/04/14 (TECHNICIAN)