

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-131-20222-00-00  
Spot: N2N2SE Sec/Twnshp/Rge: 27-1S-14E  
2310 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: STRAHM Well #: 2-27  
County: NEMAHA Total Vertical Depth: 3958 feet

Operator License No.: 31439  
Op Name: KINNEY OIL COMPANY  
Address: 1401 17TH ST STE 870  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3009		100 SX
SURF	8.625	267		165 SX
T1	2.875	2902		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/17/2013 5:00 PM  
Plug Co. License No.: 30141 Plug Co. Name: SUMMIT DRILLING COMPANY  
Proposal Rcvd. from: \_\_\_\_\_ Company: SUMMIT DRILLING COMPANY Phone: (620) 343-3278

Proposed Plugging Method: 50' PLUG ACROSS PRODUCING ZONES, 50' PLUG AT KC, 300' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE  
Date/Time Plugging Completed: 12/17/2013 6:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

RAN DRILL PIPE DOWN TO 2000' AND PUMPED 15 SACKS OF CEMENT. PERFORATED THE PRODUCTION CASING AT 1200' AND 300'. RAN THE DRILL PIPE BACK IN TO 1200' AND PUMPED 15 SACKS OF CEMENT. PULLED THE DRILL PIPE OUT OF THE HOLE AND HOOKED ON TO THE PRODUCTION CASING AND PUMPED 100 SACKS OF CEMENT TO THE SURFACE.

Perfs:

Top	Bot	Thru	Comments
2818	2830		KCC WICHITA MAR 26 2014 RECEIVED RECEIVED MAR 20 2014 KCC Chanute Dist. #3 TH

Remarks:

Plugged through: DP

District: 03

Signed Taylor Herman  
4/02/14 (TECHNICIAN)